App F IX-4

Previous References

194
(Ml)

File No 43-48
Serial Nos 3 4

Later References
CM KCP 272/54

GENERAL AND REVENUE SECRETARIAT

Serial Nos Two

P10/E

Part B for Sept 48

SUBJECT Estimate for Rs 7,625 or Laying [redacted] underground Sewer lines to the layout formed by Raja Ram Mohan Roy Road Lal-Bagh Road Bangalore

---

L 2047-5 / 1-9-48

To

Municipal Commissioner Bangalore through the president

C E for Roads and Buildings

Chairman C.I.T.B Bangalore

Comptroller to Govt

Sanctioned

6392

From the Municipal Commissioner Bangalore City

No C 503 dt 19-4-48

Ltr for sanction an estimate for Rs 8990 for laying underground sewer lines in the Layout formed by Raja Ram Mohan Roy Avenue Lalbagh road Bangalore City

1) The estimate will be sent herewith to the Chief Engineer for Roads and Buildings for scrutiny and remarks

EXECUTIVE ENGINEER PE BLORE
No 4464
DATE 6/5
BANGALORE

6/5/48

24/4/48

2) Forwarded with Compliments to the Chief Engineer for Roads and Buildings for favour of scrutiny and return

By Hand 28/4/48

Rc Rcndal Memo dt 24/4/48
for Secretary to Govt
Rev Dept

2nd Govt

3)

U O No 7 Dated, 10/7/48

Returned with compliments

2 The estimate for Rs 7,625/- is corrected and scrutinised It is in order

10/7

CHIEF ENGINEER FOR
ROADS AND BUILDINGS

for Secretary to Govt)
Revenue Department)

Ml 6392 Laying underground sewer lines to the layout formed by Rajaram Mohan Roy Lemon Lalbagh Road, Bangalore

---

4) The estimate for Rs 8970 referred to in para 1 above has been scrutinised & corrected to Rs 7625- by the Chief Engineer for Roads & Buildings. It may now be submitted to the Minister for City Municipalities & Muzrai. The cost would be met out of the deposits made by the Lemon referred to below.

Asst
12/7/48

5) May be approved

SSG
14/7

new sig
13/7/48

THE MINISTER FOR CITY MUNICIPALITIES AND MUZRAI
No 3 EE --
Date 21-7-1948

new sig
Minister for Muzrai

6) I agree

18/7

7) [illegible] 19 7 48

7/8

8/8

8) Asst to Mr [illegible]

Laying underground sewer lines to the layout formed by Rajasabha Mohan Roy Avenue, Lalbagh Road, Bangalore

MC 6392

4) Submitted with a draft GC for approval

Issue
of
18/8/48

Issued in GC. No. 2047 - 57/MC
43-48-4 dt 1-9-48

To The M.C. Engineer Bangalore City
The Chief Engineer Roads & Bldgs
The Chairman City Improvement
Trust Bd Bangalore
The Comptr Bangalore

B

10/9/48

BANGALORE CITY MUNICIPALITY

ml 43-48-3

A6 C 503/45

MUNICIPAL OFFICES
BANGALORE CITY

Dated 19th April

SAFI DARASHAH Esq B A
MUNICIPAL COMMISSIONER
BANGALORE CITY

Syed Abdul Aleem Esq , B A ,
Secretary to the Government of Mysore,
Revenue Department, Bangalore

SIR

Subject - Laying underground sewer lines to the layout formed by Raja Ram Mohan Roy Union, Lalbagh Road, Bangalore

====

In enclosing herewith a copy of the Council resolution dated 3-4-1948 sanctioning the estimate for Rs 9000/- for the above work furnished by the Chairman, City Improvement Trust Board, I have the honour to state that the expenditure in this regard will be met out of the deposits made by the Union and by the individuals who owns sites in the layout

2 I request you therefore kindly to obtain early sanction of Government to the resolution of the Council for placing the amount at the disposal of the Chairman City Improvement Trust Board for needful

The connected papers including the plan and estimate are sent herewith for favour of reference and return

I have the honour to be,
Sir,
Your most obedient servant,

Municipal Commissioner

Forwarded with compliments

Honorary President

hsr/-

Proceedings of the meeting of the Bangalore City Municipal Council dated 3-4-48

22 Estimate for Rs 9,000/- for laying underground sewer lines in the Raja Ram Mohan Union Layout (The amount has been deposited by the Layout owners)

Resolution - Sanctioned

Sd/- K Shamaraja Iyengar,
Honorary President

"Copy"

Municipal Commissioner

hsr/-

No. 1799/47

OFFICE OF THE CHAIRMAN,
City Improvement Trust Board,
Dated, Bangalore, the 12th January 48

To

The Municipal Commissioner,
City Municipality,
BANGALORE

Sir,

Re Estimate for laying under-ground severs to Raja Ram Mohan Roy lay-out

In continuation of this Office letter No 3254 - dated 2-6-1947 stating that the question of draining the above layout by gravitation is under progress and requesting you to insist on the owners of sites keeping the basement of houses 3 feet above the present ground level, I have the honour to state that the sub-main for linking the Public - Office Main which is the out fall for this layout has been altered and taken in one of the main roads of the layout An estimate amounting to Rs 9,000/- for providing under-ground drainage to the layout is herewith forwarded The report accompanying the estimate explains the details of the Scheme The estimate may kindly be countersigned and the funds placed at the disposal of this Division to enable the work being carried out soon

I have etc,

C N Narasimha Rao
CHAIRMAN

CITY MUNICIPAL OFFICE BANGALORE CITY
17 JAN
Ass. A8

A6 c 503/48
13/1

Copy of above forwarded to the Commercial Engineer for estimate may be checked and submitted for passing further action

30-1-48

27/1/48

REPORT to accompany the estimate for providing underground drainage to the Lay-out of Rajaram Mohan roy in - S No 85-86 of Dodbylakhana, Bangalore City

Amount of Estimate = Rs.9,000/-

The accompanying estimate is prepared for providing underground sewers to the layout formed by M/s Rajaram Mohanroy union situated to the sout of Lalbagh Road and to the west of Lonley Tope Road

It comprises of two parts

PART I - provides the cost for laying a 7" dia sewer line in the 1st Main Road to a length of 635 Rft including 22 junctions of 7" x 4"(required for house connections). 4 Manholes of depths varying from 7' to 8' have also been provided for in the estimate The tendered rate for the work of linking Public Office main to the Main sewer has been adopted in the estimate in view of the increased - depth of excavation adopted for a bigger diameter of the Submain.

According to the original sanctioned estimate for laying the Sub-main for linking Public Office main to the Main Ovoid sewer, this layout as well as Mr Thammiah's layout could not be sewered except by pumping means

The Sub main has now been proposed to be run at a much lower level and the design and alignment has been suitably altered so that both these layouts could now be drained without resorting to pumping by taking the sub-main along one of the main roads The cost of the estimate for Part I amounts to Rs 4,920/- as per accepted tender and will have to be credited to the work of linking Public -

Public Office Main

The estimate Part II is for providing and laying a 7" dia S I pipe line to a length of 945 Rft including 25 S I junction pipes of 7" x 4" dia (required for house connections) with 4 manholes of depths varying from - 3' to 8' The current schedule of rate has been provided for the several items of work in this estimate and the estimate amounts to Rs 4,000/- which amount will - have to be revised on accepting quotations for the work

The total cost of the underground drainage scheme for the above layout for s out to Rs 9,000/- including establishment tools and plant charges at 12½%

The work of linking Public Office Main in the - locality is under progress and the work relating to the above estimate could also be taken up simultaneously if sanctioned

Early sanction to the estimate is therefore solicited

R Mathavan
ENGINEER OFFICER

Pss/2

Proceedings of the Govt of H.H. the Maharaja of Mysore
~~A.D.~~ (Revenue Department)

Ml 43-48-4

Read -

Letter No A6C-503/45 dated 2e 19th April 1948 from the Municipal Commr, Bangalore City Municipality requesting sanction of Govt to the resolution of the Bangalore City M.C. dated the 3rd April 1948 to the effect that the estimate for Rs 9000 for laying underground sewer lines to the layout formed by Rajasam Mohan Roy Lines Lalbagh Road, Bangalore may be sanctioned and that the amount may be placed at the disposal of Chairman, City Improvement Trust Board Bangalore for needful being done and adding that the expenditure in this regard will be met out of the deposits made by the aforesaid persons and by the individuals who own sites in the layout

2 Re G No 7 dated the 10th July 1948 from the Chief Engineer for Roads & Buildings on the subject

GO No L 2647-57 dated 1-9-1948

The estimate is sanctioned for Rs 7,625/-
(Rupees Seven thousand six hundred and twenty five only)

as corrected by the Chief Engineer for Roads and Buildings, the expenditure being met from the source pointed out by the Municipal Commissioner

2 Approval is also accorded to the proposal to place the above-mentioned amount at the disposal of the Chairman City Improvement Trust Board, Bangalore, for needful action being taken in the matter.

By order
for Secretary to Govt
of the Revenue Dept
16 8 48 Spr 16-8-1948

To
The Municipal Commissioner, Bangalore City, Mlhy (through the Pdt) with estimate & sketch
The Chief Engineer for Roads & Buildings, Bangalore
The Chairman City Improvement Trust Board, Bangalore
The Comptroller to Govt